

- (2) The Chief Electrical Engineer reserves to himself the right to refuse the lowest or any tender, whole or part, without assigning any reason therefor.

SCHEDULE I.—*Timber.*

1. Junglewood scantlings, free from knots, cracks, sap or white wood, etc.
 

|                                            |              |
|--------------------------------------------|--------------|
| (a) 3"×4"×13 R.ft.=4,160 R.ft. .. .. .     | 320 Pieces.  |
| (b) 3"×4"×11' or multiples thereof .. .. . | 49,840 R.ft. |
2. Junglewood round poles 4" to 5" dia. in lengths of:—
 

|                     |            |
|---------------------|------------|
| (a) 12 ft. .. .. .  | 6,500 Nos. |
| (b) 15 ft. .. .. .  | 1,650 "    |
| (c) 10½ ft. .. .. . | 1,650 "    |
| (d) 9 ft. .. .. .   | 3,300 "    |
| (e) 8½ ft. .. .. .  | 2,400 "    |

SCHEDULE II.—*Hardware Materials.*

1. Galvanized Iron Corrugated iron sheets, 24 gauge, 2'-8"×6' long .. 2,700 Nos.
2. Cement Asbestos Corrugated Sheets, in 6' lengths .. 43,200 S.ft.
3. Galvanized Iron Bolts and Nuts with washers, ½" .. 160 gross.
4. 2½" wire nails .. .. . 200 lbs. or 200 gross.
5. 8" long square nails .. .. . 100 lbs. or 150 gross.
6. Galvanized Iron Hook-Bolts 7"×5/16" .. 300 gross.
7. Bitumen and Asbestos Felt Washers .. 300 "

SCHEDULE III.—*Miscellaneous.*

1. Bamboo Thattics 5'×8' .. .. . 6,91,000 S.ft.
2. Bamboo Baskets (Mankaris) for carrying earth, etc. .. 10,000 Nos.
3. Doors of bamboo matting with braces. 2'-8"×5'-6" size .. 1,600 "
4. Charcoal bags, 1st quality, free from dust, stones, etc., 80 lbs. nett per bag. 500 bags.

L. A. H. WINCKLER,  
For Chief Electrical Engineer.

OFFICE OF THE SUPERINTENDING ENGINEER, ELECTRICAL DEPARTMENT,  
BANGALORE.

*Notification dated 12th October 1938.*

Notice is hereby given that sealed tenders will be received at the Office of the Superintending Engineer, Electrical Department, Bangalore, upto 3 P.M. on the 12th November 1938, for constructing Electrical Buildings at Sidlaghatta Town. An approximate estimate of quantities is given below. These quantities are not guaranteed. The works should be completed by the end of February 1939.

2. The plans, detailed estimate and conditions may be seen at the Office of the Superintending Engineer, Electrical Department, Bangalore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms, which may be obtained from the Superintending Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 350 cash or Government promissory notes, as earnest money and be superscribed "Tender for constructing Electrical Buildings at Sidlaghatta Town" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason for the rejection of any tender.

6. Within eight days (8) of the acceptance of any tender the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be pasted on to the Notice Board in the Superintending Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on the rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Public Works Department or those fixed by the Superintending Engineer, after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of work, etc., and in all disputes of any kind, the decision of the Superintending Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than the estimated rate, will not be accepted.

13. Charges on account of water, scaffolding materials, implements for setting out, barricading, clearing site, supply of work, etc., that may be found necessary during execution will not be paid for separately, but should be borne by the contractor.

Abstract of the estimate of the probable cost of constructing combined Station, Office and Stores Building at Sidlaghatta Town.

| Item No. | Description of work                                                                                                                                              | Unit  | Estimate rate | Tendered rate in |           |
|----------|------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|---------------|------------------|-----------|
|          |                                                                                                                                                                  |       |               | Figures          | Words     |
|          |                                                                                                                                                                  |       |               | Rs. a. p.        | Rs. a. p. |
| 1        | Earthwork excavation and filling in basement ..                                                                                                                  | C.yd. | 39            |                  |           |
| 2        | Stone jelly in lime mortar concrete for foundation.                                                                                                              | C.ft. | 361           |                  |           |
| 3        | Stone in lime foundation and basement, including through stones 6 ft. apart in every course ..                                                                   | "     | 869           |                  |           |
| 4        | Burnt brick in clay superstructure ..                                                                                                                            | "     | 1,298         |                  |           |
| 5        | Burnt brick in mortar superstructure ..                                                                                                                          | "     | 144           |                  |           |
| 6        | Stone slabs 6" thick, roughly dressed and fixed in mortar ..                                                                                                     | S.ft. | 177           |                  |           |
| 7        | Stone slabs 3" thick, exposed parts one line dressed and set in mortar ..                                                                                        | S.ft. | 7             |                  |           |
| 8        | Brick in mortar pillars $1\frac{1}{2}$ square, $9\frac{1}{2}$ ft. high including stone base and capital and cement plastering $\frac{1}{2}$ " thick ..           | Each  | 4             |                  |           |
| 9        | Chunam plastering 2 coats ..                                                                                                                                     | Sqr.  | 29'00         |                  |           |
| 10       | Cement pointing with thread lines ..                                                                                                                             | "     | 1'88          |                  |           |
| 11       | White and colour washing, 2 coats ..                                                                                                                             | "     | 31'00         |                  |           |
| 12       | Brick cornice 6" projection as per design ..                                                                                                                     | R.ft. | 158           |                  |           |
| 13       | Brick in mortar parapet wall 9" thick, as per design ..                                                                                                          | "     | 155           |                  |           |
| 14       | Chunam moulding 6" x $\frac{1}{2}$ " around ventilators ..                                                                                                       | "     | 77            |                  |           |
| 15       | Chunam moulding in front wall between pillars as per design ..                                                                                                   | No.   | 4             |                  |           |
| 16       | Cement concrete flooring $1\frac{1}{2}$ " thick on 4" concrete bed and cement plastered $\frac{1}{2}$ " thick with red coloured cement ..                        | Sqr.  | 6'00          |                  |           |
| 17       | Terrace filled with brick in surki mortar with wedge-shaped R. C. joists with 3" to 6" lime concrete, two coats flat tiles surface and ceiling lime plastered .. | "     | 6'75          |                  |           |
| 18       | Steel work fixed complete (Tata's tested) with 2 coats of painting ..                                                                                            | Cwt.  | 8'50          |                  |           |
| 19       | T. W. doors panelled $1\frac{1}{2}$ " thick shutters with fixtures, etc., complete as per design ..                                                              | S.ft. | 92            |                  |           |
| 20       | T. W. glazed windows $1\frac{1}{2}$ " thick shutters with iron bars, $\frac{1}{2}$ " dia. fixtures, etc., complete as per drawing ..                             | "     | 70            |                  |           |
| 21       | T. W. Ventilators glazed, with iron bars ..                                                                                                                      | "     | 27            |                  |           |
| 22       | Silicate painting, two coats ..                                                                                                                                  | Sqr.  | 12'87         |                  |           |
| 23       | Fixing wire-gauge shutters with T. W. battens and spring hinges complete as per drawing ..                                                                       | S.ft. | 63            |                  |           |
| 24       | Rain water down G. I. pipes, fixed complete (4" x 2") (square) including painting ..                                                                             | R.ft. | 78            |                  |           |
| 25       | Brick in lime mortar and stone slabs with chunam plastering, etc., complete for brackets ..                                                                      | No.   | 10            |                  |           |
| 26       | Clearing site and levelling the ground ..                                                                                                                        | L. S. | ..            |                  |           |

Abstract of the estimate for constructing a single block of Operator's quarters with half unit of latrine, at Sidlaghatta Town.

| Serial No. | Description                                                     | Unit  | Quantity | Tendered rate in |           |
|------------|-----------------------------------------------------------------|-------|----------|------------------|-----------|
|            |                                                                 |       |          | Figures          | Words     |
|            |                                                                 |       |          | Rs. a. p.        | Rs. a. p. |
| 1          | Earthwork excavation and filling in basement ..                 | C.yd. | 33       |                  |           |
| 2          | Concrete stone jelly in lime mortar ..                          | C.ft. | 315      |                  |           |
| 3          | Stone in clay foundation and basement, including bond stones .. | "     | 705      |                  |           |

| Serial No. | Description                                                                                                   | Unit  | Quantity | Rate tendered in |           |
|------------|---------------------------------------------------------------------------------------------------------------|-------|----------|------------------|-----------|
|            |                                                                                                               |       |          | Figures          | Words     |
|            |                                                                                                               |       |          | Rs. a. p.        | Rs. a. p. |
| 4          | Burnt brick in clay superstructure .. ..                                                                      | C.ft. | 1,637    |                  |           |
| 5          | Burnt brick in mortar .. ..                                                                                   | "     | 400      |                  |           |
| 6          | Stone slabs 4" thick, roughly dressed and fixed in mortar .. ..                                               | S.ft. | 119      |                  |           |
| 7          | Chunam plastering, 2 coats .. ..                                                                              | Sqr.  | 42.22    |                  |           |
| 8          | Cement pointing with thread lines .. ..                                                                       | Sqr.  | 1.09     |                  |           |
| 9          | White and colour washing, two coats .. ..                                                                     | "     | 43.31    |                  |           |
| 10         | Constructing sinks .. ..                                                                                      | No.   | 1        |                  |           |
| 11         | Providing and fixing stones mortar and pestle ..                                                              | No.   | 1        |                  |           |
| 12         | Brick in mortar plain, 6" cornice .. ..                                                                       | R.ft. | 60       |                  |           |
| 13         | Binding wall 1½' x ½' brick in mortar with chunam plaster, etc., complete .. ..                               | R.ft. | 60       |                  |           |
| 14         | Roofing with first class Mangalore Tiles on T. W. rcepers 2" x 1" including wood oiling to rcepers .. ..      | Sqr.  | 7.50     |                  |           |
| 15         | Ventilating tiles, fixed, complete .. ..                                                                      | No.   | 2        |                  |           |
| 16         | Ridge tiles set in mortar and cement pointed ..                                                               | R.ft. | 24       |                  |           |
| 17         | T. W. wrought and put up with 2 coats of wood oiling .. ..                                                    | C.ft. | 28.40    |                  |           |
| 18         | T. W. battened doors with 1" thick shutters, fixtures, etc., complete as per drawing .. ..                    | S.ft. | 156      |                  |           |
| 19         | T. W. battened windows with 1" thick shutters ½" dia. iron bars fixtures, etc., complete as per drawing .. .. | "     | 78       |                  |           |
| 20         | T. W. shelves with shutters, planks, fixtures, etc., complete as per drawing .. ..                            | "     | 48       |                  |           |
| 21         | Chocolate painting, 2 coats .. ..                                                                             | Sqr.  | 5.85     |                  |           |
| 22         | Flooring with 1" cement concrete on 3" lime concrete and top ½" thick red coloured cement plaster .. ..       | "     | 5.00     |                  |           |
| 23         | Stone pillars 8" x 8" dressed 8' high with base and capital complete .. ..                                    | No.   | 2        |                  |           |
| 24         | R. S. girders including painting .. ..                                                                        | Cwt.  | 4.00     |                  |           |
| 25         | Roofing with R. C. C. slabs 3" thick and finished as per specification .. ..                                  | Sqr.  | 0.56     |                  |           |
| 26         | Plain 9" cornice brick in lime .. ..                                                                          | R.ft. | 20       |                  |           |
| 27         | Plain brick in lime parapet wall 9" wide and 15" high, as per design .. ..                                    | "     | 20       |                  |           |
| 28         | Boxing girders with brick in cement, plastering, etc., complete .. ..                                         | R.ft. | 20       |                  |           |
| 29         | Levelling the ground .. ..                                                                                    | L. S. | ..       |                  |           |

## For constructing a Latrine.

|    |                                                                                   |       |      |
|----|-----------------------------------------------------------------------------------|-------|------|
| 1  | Earthwork excavation and filling in basement ..                                   | C.yd. | 3    |
| 2  | Burnt stone in lime mortar foundation .. ..                                       | C.ft. | 50   |
| 3  | Burnt brick on lime mortar superstructure .. ..                                   | C.ft. | 320  |
| 4  | Chunam plastering 2 coats .. ..                                                   | Sqr.  | 4.70 |
| 5  | Cement pointing with thread lines .. ..                                           | "     | 0.34 |
| 6  | White and colour-washing, 2 coats .. ..                                           | "     | 5.04 |
| 7  | Cement plastering, 2 coats .. ..                                                  | "     | 0.60 |
| 8  | Tar washing, 2 coats .. ..                                                        | "     | 0.38 |
| 9  | Flooring with 1" cement concrete on 3" lime concrete and top cement plaster .. .. | "     | 0.30 |
| 10 | Fixing outlets, constructing drains, etc. .. ..                                   | L. S. | ..   |
| 11 | Providing galvanized iron sheets tubes 12" x 6" including tarring .. ..           | No.   | 3    |

Abstract of the estimate of the probable cost of constructing one block of four Linemen's quarters with one unit of latrine at Siddaghatta Town.

|   |                                                                                    |       | Rs. a. p. | Rs. a. p. |
|---|------------------------------------------------------------------------------------|-------|-----------|-----------|
| 1 | Earthwork excavation and filling in basement, including watering and ramming .. .. | C.yd. | 29        |           |
| 2 | Concrete stone jelly in lime mortar .. ..                                          | C.ft. | 309       |           |
| 3 | Stone in clay foundation and basement including bond stones 6' apart .. ..         | "     | 741       |           |
| 4 | Burnt brick in clay superstructure .. ..                                           | "     | 1,538     |           |
| 5 | Burnt brick in lime mortar, superstructure .. ..                                   | "     | 537       |           |

| Serial No.               | Description                                                                                                            | Unit  | Quantity | Rate tendered in |           |
|--------------------------|------------------------------------------------------------------------------------------------------------------------|-------|----------|------------------|-----------|
|                          |                                                                                                                        |       |          | Figures          | Words     |
|                          |                                                                                                                        |       |          | Rs. a. p.        | Rs. a. p. |
| 6                        | Stone slabs 4" thick, roughly dressed and fixed in lime mortar .. .. .                                                 | S.ft. | 141      |                  |           |
| 7                        | Chunam plastering, 2 coats .. .. .                                                                                     | Sqr.  | 44       |                  |           |
| 8                        | Cement pointing with thread lines .. .. .                                                                              | "     | 1.50     |                  |           |
| 9                        | White and colour-washing, 2 coats .. .. .                                                                              | "     | 45.50    |                  |           |
| 10                       | Roofing with first class Mangalore Tiles on T. W. reapers including wood-oiling to reapers 2" x 1" ..                  |       | 15       |                  |           |
| 11                       | Ridge tiles set in mortar and cement-pointed ..                                                                        | R.ft. | 63       |                  |           |
| 12                       | Ventilating tiles fixed complete .. .. .                                                                               | No.   | 16       |                  |           |
| 13                       | T. W. wrought and put up including wood oiling, 2 coats .. .. .                                                        | C.ft. | 52.52    |                  |           |
| 14                       | T. W. battened doors with 1" thick shutters and all fixtures complete, as per drawing ..                               | S.ft. | 156      |                  |           |
| 15                       | T. W. battened windows with 1" thick shutters 1/2" dia. iron bars and fixtures, etc., complete, as per drawing .. .. . | "     | 75       |                  |           |
| 16                       | T. W. cup-boards with shutters 1" thick and planks, fixtures, etc., complete, with 3" x 4" frame ..                    | "     | 60       |                  |           |
| 17                       | Chocolate painting, 2 coats .. .. .                                                                                    | Sqr.  | 5.50     |                  |           |
| 18                       | Constructing sinks complete, with out-let pipes ..                                                                     | No.   | 4        |                  |           |
| 19                       | Providing and fixing stone mortar and pestle ..                                                                        | No.   | 4        |                  |           |
| 20                       | Flooring with 3" lime concrete, 1" cement concrete and top plastered with 1/2" thick cement plastering .. .. .         | Sqr.  | 8.00     |                  |           |
| 21                       | Levelling the ground all round .. .. .                                                                                 | L. S. |          | 10 0 0           |           |
| For constructing Latrine |                                                                                                                        |       |          |                  |           |
| 1                        | Earthwork excavation and filling in basement, complete .. .. .                                                         | C.yd. | 4        |                  |           |
| 2                        | Burnt stone in lime mortar foundation and basement .. .. .                                                             | C.ft. | 150      |                  |           |
| 3                        | Burnt brick in mortar superstructure .. .. .                                                                           | "     | 193      |                  |           |
| 4                        | Chunam plastering, 2 coats .. .. .                                                                                     | Sqr.  | 4.91     |                  |           |
| 5                        | Cement pointing with thread lines .. .. .                                                                              | "     | 0.56     |                  |           |
| 6                        | White and colour-washing, 2 coats .. .. .                                                                              | "     | 5.47     |                  |           |
| 7                        | Cement plastering 1/2" thick .. .. .                                                                                   | "     | 0.80     |                  |           |
| 8                        | Tar washing, 2 coats .. .. .                                                                                           | "     | 0.63     |                  |           |
| 9                        | Flooring with 3" lime concrete, 1" cement concrete and top finished with 1/2" cement plaster ..                        | "     | 0.38     |                  |           |
| 10                       | Fixing outlets, constructing drains, etc. .. ..                                                                        | L. S. |          |                  |           |
| 11                       | Providing galv. iron sheet tubs 12" x 6" complete, with tarring .. .. .                                                | No.   | 6        |                  |           |

L. A. H. WINCKLER,  
Superintending Engineer.

GOVERNMENT OF MYSORE, STORES PURCHASE COMMITTEE, BANGALORE.

No. S. P. C. 9731-40, dated 25th October 1938.

To

The Firms dealing in Cyclostyle Machines.

Enquiry No 3085.

CYCLOSTYLE MACHINES.

DEAR SIR/GENTLEMEN,

Please be good enough to intimate your best prices and the earliest time of delivery for the materials described in the attached schedule, in the form printed below.

It should be distinctly understood that the acceptance by us of your quotation will be subject to the following conditions:—

Withdrawal from the quotation after it is accepted or failure to make the supply within the specified time or according to specifications will entail cancellations of the order and purchases being made at your expense from other sources in addition to the levy of a penalty of 3 per cent of the value of the order as and by way of liquidated damages. In such an event, the Stores Purchase Committee reserve the right to remove your name from the list of approved firms.